Reduction of Tile Heating, Particle, and Carbon Sources with the New DIII-D Divertor 2000

by C.J. Lasnier* for C.B. Baxi, M.A. Mahdavi, G.D. Porter,* D.G. Whyte,[†] W.P. West, N.S. Wolf,* and the DIII-D Team

> *Lawrence Livermore National Laboratory [†]University of California, San Diego, California

Presented at the American Physical Society Division of Plasma Physics Meeting Quebec City, Canada

October 23-27, 2000



2000APS/wj



- Local tile heating was reduced by tile alignment and contouring.
- Modeling indicates that baffling plays a major role in reduced core carbon contamination.
- Pump and baffle are effective.



Mis-aligned tiles suffer strong erosion



Divertor-2000 built for core density and impurity control





New system pumps the inner strike point, outer pump existing



Accurate alignment and smaller gaps reduce tile edge heating





06 alignment reduces hot spots

Inner Strike position moved from contoured to flat tiles



Horizontal surface temperature profiles from IRTV image show much less peaking on the contoured tiles





Long pulse fixed strike locally heats the ceiling





No increase in core carbon seen with high tile temperature



At 1500 K, Carbon yield ~ 4x physical sputtering



J. Hogan et al. GP1.143 this meeting

*Radiation-Enhanced Sublimation



UEDGE modeling indicates that baffling plays a major role in lower core carbon with divertor 2000



Carbon concentration is reduced compared to previous operation





UEDGE matches measurement of core ionization





DIII-D shot #101560 and UEDGE simulation tpd30

UEDGE predicts core ionization reduced by baffle without pumping

• UEDGE matches measurement of core ionization in baffled discharge





DIII-D shot #101560 and UEDGE simulation tpd30



Density control achieved with the new Divertor 2000



- Local tile heating was reduced on the new inner wall tiles by alignment and contouring.
- Modeling indicates that baffling plays a major role in reduced core carbon contamination.
- Many discharges show reduced carbon content.
- The new upper inner pump and baffle are installed and working. Pumping is effective as predicted.

